CUTTING LIST

mark	item	on	section	grade	length	qty	cut from (stock x length)	machining	holes	sheet
P4-T1	SB1 packer	SB1	70x147	C24	2559	1	75x147 x 2700	ripped 70 from 75	8	STT-01
P4-T2	SB2 packer	SB2	66x147	C24	2866	1	75x147 x 3000	ripped 66 from 75	9	STT-01
P4-T3	SB2 binder	SB2	45x254	C24	2709	1	47x295 x 3000	ripped 45 from 47, ripped 254 from 295 (next stock size - joiner to confirm)	9	STT-01
P4-T4	SB2 top plate	SB2	50x145	C24	2905	1	50x145 sawn x 3000	ripped to 145	10	STT-02
P4-T5	SC1 jamb plate	SC1	38x140	C16	2462	1	38x140 x 2700	as stock - no ripping	3	STT-02
P4-T6	SC1 jamb plate	SC1	30x140	C24	2462	1	38x140 x 2700	ripped 30 from 38 (next stock size - joiner to confirm)	3	STT-02
P4-T7	SC2 jamb plate	SC2	38x89	C16	2462	2	38x89 x 2700	as stock - no ripping	3	STT-03
P4-T8	SC3 jamb plate	SC3	38x140	C16	2462	2	38x140 x 2700	as stock - no ripping	3	STT-03
P4-T9	SB4 packer	SB4	14x140	marine ply	5540	1	2440 x 1220 sheet, 14 thick	rip 140 strips	9	STT-03
P4-T10	SB4 head binder (a)	SB4	38x140	C16	2813	1	38x140 x 3000	as stock - no ripping	5	STT-04
P4-T11	SB4 head binder (b)	SB4	38x140	C16	2813	1	38x140 x 3000	as stock - no ripping	4	STT-04
P4-T12	PC1 / PC2 jamb plate	PC1, PC2	38x140	C16	2400	2	38x140 x 2700	as stock - no ripping	3	STT-04

Lengths are the finished piece lengths from the model; stock lengths allow 10 for squaring the ends. Machining from the spec where it states it, otherwise the next stock size up (joiner to confirm). Treatment: to the project specification (by others) - treat cut ends and holes.

FIXINGS THROUGH EACH PIECE (PER PIECE X PIECES)

mark	fixing	no.	hole	counterbore
P4-T1	M12x90 8.8 bolt set (timber)	8 x 1	14 through	60 x 13 on the W face
P4-T2	M12x130 8.8 bolt set (timber)	9 x 1	14 through	-
P4-T3	M12x130 8.8 bolt set (timber)	9 x 1	14 through	60 x 13 on the E face
P4-T4	M12x50 coach screw + washer	10 x 1	pilot 8 x 42.2 from underside	-
P4-T5	M12 8.8 threaded rod 165 + 2 nuts (timber jamb)	3 x 1	14 through	60 x 18 on the W face
P4-T6	M12 8.8 threaded rod 165 + 2 nuts (timber jamb)	3 x 1	14 through	60 x 18 on the E face
P4-T7	M12 8.8 threaded rod 173 + 2 nuts (timber jamb)	3 x 2	14 through	60 x 18 on the face away from the steel (E / W)
P4-T8	M12 8.8 threaded rod 173 + 2 nuts (timber jamb)	3 x 2	14 through	60 x 18 on the face away from the steel (N / S)
P4-T9	M12x55 stud welded to RHS + nut + washer	9 x 1	14 through	-
P4-T10	M12x55 stud welded to RHS + nut + washer	5 x 1	14 through	60 x 16 on the top
P4-T11	M12x55 stud welded to RHS + nut + washer	4 x 1	14 through	60 x 16 on the top
P4-T12	M12x160 8.8 bolt set (timber)	3 x 2	14 through	60 x 18 on the face away from the steel (N / S)

EDGE / END DISTANCE AND DATA CHECKS (EN 1995-1-1 8.5: end 7d, edge 4d)

FLAG: SB2 binder 45x254 C24: end 53.7 < 7d 84 - 1 hole at 53.7 from the S end
FLAG: SB2 top plate 50x145 C24: edge 44 < 4d 48 - 5 holes at 99.7, 699.7, 1299.7, 1899.7, 2499.7 from the S end
FLAG: SB2 top plate 50x145 C24: edge 31 < 4d 48 - 5 holes at 399.7, 999.7, 1599.7, 2199.7, 2799.7 from the S end
FLAG: SC2 jamb plate 38x89 C16: edge 44 < 4d 48 - 3 holes at 300, 1231, 2162 from the bottom end

SHEET INDEX

sheet	title
P4-STT-00	Steel timber packing schedule
P4-STT-01	SB1 packer, SB2 packer, SB2 binder
P4-STT-02	SB2 top plate, SC1 jamb plate
P4-STT-03	SC2 jamb plate, SC3 jamb plate, SB4 packer
P4-STT-04	T10 to T12

NOTES

1. **FOR APPROVAL - NOT FOR FABRICATION until the engineer has approved the TLS details and returned the steel drawings.**
2. ALL TIMBER SUBJECT TO SITE MEASURE AGAINST THE ERECTED STEEL BEFORE DRILLING.
3. Timber: strength-graded to BS EN 14081, C16 / C24 as scheduled, regularised; preservative treatment to the project specification (by others). Treat all cut ends and drilled holes.
4. Holes: bolts, rods and studs drilled d + 2 (M12 = 14), square to the face. Counterbores flat-bottomed (Forstner), concentric with the hole. Coach screws pre-drilled per EN 1995-1-1 8.7.
5. Running dimensions from the named reference end; across dimensions from the named edge. Dimensions in mm.
6. Bolt spacings checked against EN 1995-1-1 8.5 as set by the client: end 7d, edge 4d (M12: 84 / 48). Shortfalls are listed in red on STT-00.

REVISIONS

REV	DATE	DESCRIPTION
C03	11.10.26	Steel timber packing drawings - first issue

TLS TIMBER FRAME
Design & Manufacture
Scan: 3D model + drawings

CLIENT	PROJECT
MP Adams	MP Adams Plot 4, Eckington

DRAWING TITLE
STEEL TIMBER PACKING SCHEDULE

SCALE	SIZE	DATE	DRAWN
NTS	A3	11.10.26	TS

STATUS	DRAWING No.	REV
FOR APPROVAL	P4-STT-00	C03

Do not scale. All dimensions in mm. Check all dimensions on site.