CUTTING LIST

mark	item	on	section	grade	length	qty	cut from (stock x length)	machining	holes	sheet
P4-T1	SB1 packer	SB1	70x147	C24	2559	1	75x147 x 2700	ripped 70 from 75	8	STT-01
P4-T2	SB2 packer	SB2	66x147	C24	2866	1	75x147 x 3000	ripped 66 from 75	9	STT-01
P4-T3	SB2 binder	SB2	45x254	C24	2709	1	47x295 x 3000	ripped 45 from 47, ripped 254 from 295 (next stock size - joiner to confirm)	9	STT-01
P4-T4	SB2 top plate	SB2	50x145	C24	2905	1	50x145 sawn x 3000	ripped to 145	10	STT-02
P4-T5	SC1 jamb plate	SC1	38x140	C16	2462	1	38x140 x 2700	as stock - no ripping	3	STT-02
P4-T6	SC1 jamb plate	SC1	30x140	C24	2462	1	38x140 x 2700	ripped 30 from 38 (next stock size - joiner to confirm)	3	STT-02
P4-T7	SC2 jamb plate	SC2	38x89	C16	2462	2	38x89 x 2700	as stock - no ripping	3	STT-03
P4-T8	SC3 jamb plate	SC3	38x140	C16	2462	2	38x140 x 2700	as stock - no ripping	3	STT-03
P4-T9	SB4 packer	SB4	14x140	marine ply	5540	1	2440 x 1220 sheet, 14 thick	rip 140 strips	9	STT-03
P4-T10	SB4 head binder (a)	SB4	38x140	C16	2813	1	38x140 x 3000	as stock - no ripping	5	STT-04
P4-T11	SB4 head binder (b)	SB4	38x140	C16	2813	1	38x140 x 3000	as stock - no ripping	4	STT-04
P4-T12	PC1 / PC2 jamb plate	PC1, PC2	38x140	C16	2400	2	38x140 x 2700	as stock - no ripping	3	STT-04

Lengths are the finished piece lengths from the model; stock lengths allow 10 for squaring the ends. Machining from the spec where it states it, otherwise the next stock size up (joiner to confirm). Treatment: to the project specification (by others) - treat cut ends and holes.

FIXINGS THROUGH EACH PIECE (PER PIECE X PIECES)

mark	fixing	no.	hole	counterbore
P4-T1	M12x90 8.8 bolt set (timber)	8 x 1	14 through	60 x 13 on the W face
P4-T2	M12x130 8.8 bolt set (timber)	9 x 1	14 through	-
P4-T3	M12x130 8.8 bolt set (timber)	9 x 1	14 through	60 x 13 on the E face
P4-T4	M12x50 coach screw + washer	10 x 1	pilot 8 x 42.2 from underside	-
P4-T5	M12 8.8 threaded rod 165 + 2 nuts (timber jamb)	3 x 1	14 through	60 x 18 on the W face
P4-T6	M12 8.8 threaded rod 165 + 2 nuts (timber jamb)	3 x 1	14 through	60 x 18 on the E face
P4-T7	M12 8.8 threaded rod 173 + 2 nuts (timber jamb)	3 x 2	14 through	60 x 18 on the face away from the steel (E / W)
P4-T8	M12 8.8 threaded rod 173 + 2 nuts (timber jamb)	3 x 2	14 through	60 x 18 on the face away from the steel (N / S)
P4-T9	M12x55 stud welded to RHS + nut + washer	9 x 1	14 through	-
P4-T10	M12x55 stud welded to RHS + nut + washer	5 x 1	14 through	60 x 16 on the top
P4-T11	M12x55 stud welded to RHS + nut + washer	4 x 1	14 through	60 x 16 on the top
P4-T12	M12x160 8.8 bolt set (timber)	3 x 2	14 through	60 x 18 on the face away from the steel (N / S)

EDGE / END DISTANCE AND DATA CHECKS (EN 1995-1-1 8.5: end 7d, edge 4d)

FLAG: SB2 binder 45x254 C24: end 53.7 < 7d 84 - 1 hole at 53.7 from the S end
FLAG: SB2 top plate 50x145 C24: edge 44 < 4d 48 - 5 holes at 99.7, 699.7, 1299.7, 1899.7, 2499.7 from the S end
FLAG: SB2 top plate 50x145 C24: edge 31 < 4d 48 - 5 holes at 399.7, 999.7, 1599.7, 2199.7, 2799.7 from the S end
FLAG: SC2 jamb plate 38x89 C16: edge 44 < 4d 48 - 3 holes at 300, 1231, 2162 from the bottom end

SHEET INDEX

sheet	title
P4-STT-00	Steel timber packing schedule
P4-STT-01	SB1 packer, SB2 packer, SB2 binder
P4-STT-02	SB2 top plate, SC1 jamb plate
P4-STT-03	SC2 jamb plate, SC3 jamb plate, SB4 packer
P4-STT-04	T10 to T12

NOTES

1. **APPROVED FOR CONSTRUCTION - the engineer approved the steelwork and the TLS details on 13.10.26; fabricate to these drawings.**
2. ALL TIMBER SUBJECT TO SITE MEASURE AGAINST THE ERECTED STEEL BEFORE DRILLING.
3. Timber: strength-graded to BS EN 14081, C16 / C24 as scheduled, regularised; preservative treatment to the project specification (by others). Treat all cut ends and drilled holes.
4. Holes: bolts, rods and studs drilled d + 2 (M12 = 14), square to the face. Counterbores flat-bottomed (Forstner), concentric with the hole. Coach screws pre-drilled per EN 1995-1-1 8.7.
5. Running dimensions from the named reference end; across dimensions from the named edge. Dimensions in mm.
6. Bolt spacings checked against EN 1995-1-1 8.5 as set by the client: end 7d, edge 4d (M12: 84 / 48). Shortfalls are listed in red on STT-00.

REVISIONS

REV	DATE	DESCRIPTION
C03	11.10.26	Steel timber packing drawings - first issue
C04	13.10.26	Approved by the engineer 13.10.26 - issued for construction

TLS TIMBER FRAME
Design & Manufacture
Scan: 3D model + drawings

CLIENT	PROJECT
MP Adams	MP Adams Plot 4, Eckington

DRAWING TITLE
STEEL TIMBER PACKING SCHEDULE

SCALE	SIZE	DATE	DRAWN
NTS	A3	13.10.26	TS

STATUS	DRAWING No.	REV
CONSTRUCTION	P4-STT-00	C04

Do not scale. All dimensions in mm. Check all dimensions on site.