

## SB3 ELEVATION

Scale 1:15 | viewed from the S side, end A (W) left





### SB3 TOP FLANGE - PLAN

1:15




### END A 1:5

Detail B: fin plate FP3 welted to SB1









**cope 50 long x 25 deep top + bottom**
2 no. M16 8.8 bolts in Ø18 holes (bolts loose, site fixed)

### END B 1:5


Detail C (SC3): fin plate FP5 welted to SC3




2 no. M16 8.8 bolts in Ø18 holes (bolts loose, site fixed)

### FP4 PLATE DETAIL 1:5




**150 x 90 x 8 thk S275**
2 no. Ø18 holes
0.82 kg qty 1 on SB3
Weld: 8mm double fillet weld (both sides)
SB3 N web face for SB2 end A (A)

### HOLE SCHEDULE

| No. | FACE | X FROM A | POSITION | HOLE | PURPOSE |
|---|---|---|---|---|---|
| H1 | web | 40 | 60 below TOS | Ø18 | M16 8.8 bolt - B (FP3 on SB1) |
| H2 | web | 40 | 140 below TOS | Ø18 | M16 8.8 bolt - B (FP3 on SB1) |
| H3 | web | 2086.3 | 60 below TOS | Ø18 | M16 8.8 bolt - C (SC3) (FP5 on SC3) |
| H4 | web | 2086.3 | 140 below TOS | Ø18 | M16 8.8 bolt - C (SC3) (FP5 on SC3) |

### CUT LIST

| MARK | ITEM | GRADE | LENGTH | QTY | KG |
|---|---|---|---|---|---|
| SB3 | UB203x102x23 | S355JR | 2126.3 | 1 | 49.1 |
| FP4 | PL 150x90x8 | S275 | | 1 | 0.82 |
| **TOTAL** | | | | | **49.9 kg** |

### CONNECTIONS

Detail B: SB3 end A on SB1 - 150x90x8 S275 fin plate welded to SB1 (8mm double fillet weld (both sides)); 2 no. M16 8.8 bolts, Ø18 holes; bolt line 50 from the support face, 40 to the plate end; pitch 35/80/35; plate top 25 below TOS; beam end gap 10; cope 50 long x 25 deep top and bottom

Detail A: SB2 end A on SB3 - 150x90x8 S275 fin plate welded to SB3 (8mm double fillet weld (both sides)); 2 no. M16 8.8 bolts, Ø18 holes; bolt line 50 from the support face, 40 to the plate end; pitch 35/80/35; plate top 25 below TOS; beam end gap 10; cope 50 long x 25 deep top and bottom

Detail C (SC3): SB3 end B on SC3 - 150x90x8 S275 fin plate welded to SC3 (8mm double fillet weld (both sides)); 2 no. M16 8.8 bolts, Ø18 holes; bolt line 50 from the support face, 40 to the plate end; pitch 35/80/35; plate top 25 below TOS; beam end gap 10

### NOTES

1. **APPROVED FOR CONSTRUCTION - the engineer approved the steelwork and the TLS details on 13.10.26; fabricate to these drawings.**
2. ALL STEELWORK SUBJECT TO SITE MEASURE BEFORE FABRICATION.
3. BS EN 1090-2 EXC2, CE marked. UB S355JR (EN 10025-2), plates S275JR.
4. Holes: normal clearance (EN 1090-2 Table 11): M12 = 14, M16 = 18. Drilled or punched full size, deburred.
5. Running dimensions from end A / base underside (o = datum). Levels above FFL (model 0).
6. Coating: Hot-dip galvanised to BS EN ISO 1461 (thickness to Table 3); T-wash + paint where exposed (architect).
7. Copes: re-entrant corners radiused 10 min (BS EN 1090-2 6.7, 5 min), cut edges ground smooth.

### REVISIONS

| REV | DATE | DESCRIPTION |
|---|---|---|
| C03 | 11.10.26 | Steel fabrication drawings - first issue |
| C04 | 13.10.26 | Approved by the engineer 13.10.26 - issued for construction |

TLS TIMBER FRAME
Design & Manufacture
Scan: 3D model + drawings

| CLIENT | PROJECT |
|---|---|
| MP Adams | MP Adams Plot 4, Eckington |

DRAWING TITLE

## SB3 UB203X102X23 FABRICATION

Under the FF south wall stone leaf, SB1 -> SC3

| SCALE | SIZE | DATE | DRAWN |
|---|---|---|---|
| 1:15 / details as noted | A3 | 13.10.26 | TS |

| STATUS | DRAWING No. | REV |
|---|---|---|
| CONSTRUCTION | P4-ST-SB3 | C04 |

Do not scale. All dimensions in mm. Check all dimensions on site.